



REQUEST FOR PROPOSAL For Rehabilitation Services for Operations Sites

RFP No:	01/11/2026 NORTHERN ZONE
Title:	Provision of Rehabilitation and construction Services for IRS operations sites
Issuing Office and Address for Bid Submission:	Address: Abt Global LLC. PMI Evolve Rwanda Project KG 8 Ave, M&M Plaza, 3rd floor Gishushu Nyarutarama P. O. Box 5200; Kigali, Rwanda <u>E-mail:</u> PMI_EvolveRwanda@abtglobal.com <u>Package Markings:</u> - RFQ#: 01/11/2026- <i>[Your company name]</i> <u>E-mail:</u> PMI_EvolveRwanda@abtglobal.com
RFP Issuance Date:	13 July 2026
RFP Closing Date:	11:00 AM, July 21, 2026
Mode of Submission	Original bid documents should be sent to the contact at the address above, or sent by email to: PMI_EvolveRwanda@abtglobal.com
Anticipated Type of Award:	Firm Fixed Price Purchase Order(s)
Basis of Award:	See “Evaluation Criteria” section
Funding Agency	U.S. Department of State
Prime Contract Number:	7200AA23C00012
U.S. Department of State / Nationality (Geo) Code:	935
List of Attachments:	1. Attachment A: Prime Contract Mandatory Flow Downs 2. Attachment B: Purchase Order Terms and Conditions 3. Attachment C: List of Exceptions 4. Attachment D: Submission Checklist



Background and Purpose

Abt Global (Abt) is contracted by US Department of State, Office of Foreign Assistance (OFA) to conduct high quality Indoor Residual Spraying (IRS) programs in multiple Presidential Malaria Initiative (PMI) supported countries in Sub Saharan Africa and the Mekong region in Southern Asia. This was accomplished through what is called the PMI Evolve Project. The purpose of this project is to achieve the targets in Indoor Residual Spraying (IRS) through implementation of a high-quality IRS program, conducting comprehensive monitoring and evaluation of the IRS program, and developing national capacity to conduct IRS. Activities are carried out in full collaboration with the National Malaria Control/Elimination Programs (MOPDD).

The Purpose of this RFP is to obtain quotes and eventually enter into a Firm Fixed Price Purchase Order with one or more firm(s) for the “Provision of Rehabilitation Services” for the PMI Evolve Project 2026 spray campaign. Price Quotations are to be shared using the bid sheet attached.

To facilitate those activities, the PMI Evolve Rwanda Project is inviting interested, registered, reputable, experienced, and capable professional local contraction companies to tender for the following RFP below:

- o RFP No: 01/11/2026 - Provision of Rehabilitation and construction Services for IRS operations sites. Interested local companies with demonstrated capacity and experience of having carried out similar services with reputable public and private organizations are requested to submit their bids.

Scope of Work:

RFP No: 01/11/2026 NORTHERN ZONE

Narrative Description of the Scope of Work for construction of Operations Sites in Northern zones

This detailed scope of work outlines each phase of the activity and will ensure all aspects are precisely planned and executed. The amounts and quantity of items, materials, supplies are listed in the bid sheet. **All the work shall be completed by August 14th**

1. Nyamabuye I Operations site (Muhanga District)

I. Preliminary Works

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:
 - o 2 bags of sawdust (20 cm)
 - o 3 bags of charcoal (30 cm)
 - o 4 Wheelbarrow of Gravel (10 cm)
 - o 4 Wheelbarrow of Small stones (20 cm)
 - o 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

- **Materials and Installation:** Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.
- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support:

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms (2*2m)
- **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.



- **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
- **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
- **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.

2.Nyamabuye II Operations site (Muhanga District)

I. Preliminary Works:

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed:

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:
 - 2 bags of sawdust (20 cm)
 - 3 bags of charcoal (30 cm)
 - 4 Wheelbarrow of Gravel (10 cm)
 - 4 Wheelbarrow of Small stones (20 cm)
 - 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

- **Materials and Installation:** Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.
- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support:

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms (2*2m)
- **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
- **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
- **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
- **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.

3.Kabacuzi Operations site (Muhanga District)

I. Preliminary Works:

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed:

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:
 - 2 bags of sawdust (20 cm)
 - 3 bags of charcoal (30 cm)
 - 4 Wheelbarrow of Gravel (10 cm)
 - 4 Wheelbarrow of Small stones (20 cm)
 - 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support:



- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms(2*2m)
 - **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
 - **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
 - **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
 - **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.
-

4.Kibangu Operations site (Muhanga District)

I. Preliminary Works:

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed:

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:
 - 2 bags of sawdust (20 cm)
 - 3 bags of charcoal (30 cm)
 - 4 Wheelbarrow of Gravel (10 cm)
 - 4 Wheelbarrow of Small stones (20 cm)
 - 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support:

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms(2*2m)
 - **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
 - **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
 - **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
 - **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.
-

5.Rugendabali Operations site (Muhanga District)

I. Preliminary Works:

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed:

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:
 - 2 bags of sawdust (20 cm)
 - 3 bags of charcoal (30 cm)
 - 4 Wheelbarrow of Gravel (10 cm)
 - 4 Wheelbarrow of Small stones (20 cm)
 - 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.



- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support:

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms (2*2m)
 - **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
 - **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
 - **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
 - **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.
-

6. Kayumbu Operations site (Kamonvi District)

I. Preliminary Works:

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed:

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:
 - 2 bags of sawdust (20 cm)
 - 3 bags of charcoal (30 cm)
 - 4 Wheelbarrow of Gravel (10 cm)
 - 4 Wheelbarrow of Small stones (20 cm)
 - 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support:

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms (2*2m)
 - **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
 - **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
 - **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
 - **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.
-

7. Masoro Operations site (Rulindo District)

I. Preliminary Works:

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed:

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:
 - 2 bags of sawdust (20 cm)
 - 3 bags of charcoal (30 cm)
 - 4 Wheelbarrow of Gravel (10 cm)
 - 4 Wheelbarrow of Small stones (20 cm)
 - 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle



- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support:

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms (2*2m)
 - **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
 - **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
 - **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
 - **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.
-

8. Murambi Operation site (Rulindo District)

I. Preliminary Works

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:
 - 2 bags of sawdust (20 cm)
 - 3 bags of charcoal (30 cm)
 - 4 Wheelbarrow of Gravel (10 cm)
 - 4 Wheelbarrow of Small stones (20 cm)
 - 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support:

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms (2*2m)
 - **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
 - **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
 - **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
 - **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.
-

9. Buyoga Operations site (Rulindo District)

I. Preliminary Works

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:
 - 2 bags of sawdust (20 cm)
 - 3 bags of charcoal (30 cm)
 - 4 Wheelbarrow of Gravel (10 cm)
 - 4 Wheelbarrow of Small stones (20 cm)
 - 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)



Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms (2*2m)
 - **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
 - **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
 - **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
 - **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.
-

10.Rutare Operations site (Gicumbi District)

I. Preliminary Works

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:
 - 2 bags of sawdust (20 cm)
 - 3 bags of charcoal (30 cm)
 - 4 Wheelbarrow of Gravel (10 cm)
 - 4 Wheelbarrow of Small stones (20 cm)
 - 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms(2*2m)
 - **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
 - **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
 - **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
 - **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.
-

11.Bukure Operations site (Gicumbi District)

I. Preliminary Works

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:
 - 2 bags of sawdust (20 cm)
 - 3 bags of charcoal (30 cm)
 - 4 Wheelbarrow of Gravel (10 cm)
 - 4 Wheelbarrow of Small stones (20 cm)



- 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms(2*2m)
- **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
- **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
- **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
- **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.

12.Bumbogo site one /soak pit number one (Gasabo District)

I. Preliminary Works

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:

- 2 bags of sawdust (20 cm)
- 3 bags of charcoal (30 cm)
- 4 Wheelbarrow of Gravel (10 cm)
- 4 Wheelbarrow of Small stones (20 cm)
- 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support:

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms(2*2m)
- **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
- **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
- **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
- **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.

13.Bumbogo site one /soak pit number two (Gasabo District)

I. Preliminary Works

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:

- 2 bags of sawdust (20 cm)
- 3 bags of charcoal (30 cm)



- 4 Wheelbarrow of Gravel (10 cm)
- 4 Wheelbarrow of Small stones (20 cm)
- 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support:

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms(2*2m)
- **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
- **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
- **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
- **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.

14.Bumbogo site two /soak pit number one (Gasabo District)

I. Preliminary Works

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:

- 2 bags of sawdust (20 cm)
- 3 bags of charcoal (30 cm)
- 4 Wheelbarrow of Gravel (10 cm)
- 4 Wheelbarrow of Small stones (20 cm)
- 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support:

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms(2*2m)
- **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
- **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
- **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
- **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.

15.Bumbogo site two/ soak pit number two (Gasabo District)

I. Preliminary Works

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:

- 2 bags of sawdust (20 cm)



- 3 bags of charcoal (30 cm)
- 4 Wheelbarrow of Gravel (10 cm)
- 4 Wheelbarrow of Small stones (20 cm)
- 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms (2*2m)
 - **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
 - **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
 - **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
 - **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.
-

16. Muvumbu I Operations site (Rwamagana District)

I. Preliminary Works

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.
- **Layering:** Set up the new bio-bed by layering materials in the following order:

- 2 bags of sawdust (20 cm)
- 3 bags of charcoal (30 cm)
- 4 Wheelbarrow of Gravel (10 cm)
- 4 Wheelbarrow of Small stones (20 cm)
- 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms (2*2m)
 - **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
 - **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
 - **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
 - **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.
-

17. Muvumbu II Operations site (Rwamagana District)

I. Preliminary Works

Clean and clear the area surrounding the soak pit and the storage facility, covering approximately 30 square meters, to create a safe and organized workspace free from debris, brush, and potential hazards.

II. Setting up the Bio-bed

- Dig a new soak pit measuring 2m x 1m x 1m.
- **Installation:** Lay a provided black impermeable sheet (6.30m) on the surface and sides of the pit to prevent water permeability. Ensure the walls are smooth to avoid puncturing the sheet.



- **Layering:** Set up the new bio-bed by layering materials in the following order:

- 2 bags of sawdust (20 cm)
- 3 bags of charcoal (30 cm)
- 4 Wheelbarrow of Gravel (10 cm)
- 4 Wheelbarrow of Small stones (20 cm)
- 6 Wheelbarrow of Big Stones (20 cm)

III. Fence (4m x 4m by 1.7 height)

Materials and Installation: Provide and install an iron steel wire, Stainless Steel wire mesh (20 square meters) and 17 wooden poles to construct a new fence.

- Provide and install a wooden door (90cm x 1.7m) with a locking handle
- Provide a medium-sized padlock for the gate.
- Provide 2 kg of 8 cm nails for securing the fence structure.
- Fix the provided plastic tarpaulin (5*6m) in the wash area to prevent the water from penetrating into the soil

IV. Construction of Bathrooms, Tank Support, and Dry Lines Support

- **Bathrooms:** Provide and install 12 wooden poles to construct two separated bathrooms (2*2m)
- **Drying Lines:** Provide and fix 2 strong wooden poles to hang coveralls on drying lines.
- **Tank Support:** fill with soil in Provided 4 bags of 100kg to create a stable bed to support the water tank.
- **Hardware:** Provide 1.5 kg of nails (6-8 cm) and 1 kg of roofing nails (6-8 cm) for construction.
- **Bathroom Base:** Provide 4 wheelbarrows of small stones for the bathroom floors.

Instructions to bidders

1. All documents submitted in response to this RFP, as well as all related correspondence, will be in English or Kinyarwanda.
2. Offerors are required to fully review all instructions and specifications contained in this RFP. Failure to do so will be at the offeror's risk.
3. At any time prior to awarding the contract, should Abt Global deem it necessary to change the RFP provisions, it will provide such amendment(s) in writing. No oral instructions by any person will in any way be considered to limit, exclude, modify, or otherwise affect any terms or conditions of this solicitation, and no supplier shall rely on any such instructions.
4. Responses to technical questions will be distributed to all bidders.
5. No inquiries will be answered over the phone or in person, except for administrative clarification regarding submission format or location of the office, etc.
6. All responses to this RFP shall be submitted via email to PMI_EvolveRwanda@abtglobal.com
7. Notwithstanding any prior agreement in place between Abt and the vendor, by signing and returning this RFP and/or submitting an offer, the offeror: (a) acknowledges receipt and acceptance of all terms and conditions contained in this RFP; and (b) confirms that all information contained in the offeror's quotation (including all applicable supporting documentation) is complete (i.e., no material omission), accurate, and current.
8. Quotes from Offeror(s) on US government debarred list will not be considered.
9. A bidder is not eligible if the bidder has been debarred by the Rwanda Public Procurement Authority because:
 - a. The bidder has been prosecuted and found guilty in court including any appeals process on corruption charges, fraud, money-laundering or any other such illegal activities.
 - b. The bidder is bankrupt.
 - c. The bidder has been excluded in accordance with regional or international conventions.
 - d. The bidder has a conflict of interest.



- e. The bidder is a government owned enterprise which cannot establish that i) it is financially autonomous ii) operates under commercial law iii) is not a dependent agency of the purchaser.
 - f. The bidder is regulatorily compliant (registered with the appropriate professional bodies and fully paid up in all tax and social security obligations).
10. Bidder shall submit offer(s) with the following naming convention:
- a. E-mail subject line (no space before/after dashes “-“):
RFP# 01/11/2026-Your company name
 - b. Attachments: e.g. Quote/product literature/registration certificates etc.
RFP# XXXX-Your company name- Quote
RFP# XXXX-Your company name- Product Literature
RFP# XXXX-Your company name- Registration certificate etc.
11. Offers shall provide unit and total price per line. In case of discrepancy between unit and extended/total price, the unit price shall prevail.
12. Descriptive literature, quality standard supporting documentation, full technical specification per quoted item must be submitted with the bid. Submitted literature will be used to demonstrate compliance with the stated technical specification but shall in no way be considered to amend the quotation and the applicable RFP requirement.
13. **No advance payment should be expected by vendors from Abt Global.**
14. Abt Global reserves the right to reject bids submitted without all requested information as non-responsive.
15. Bids must be submitted either in sealed envelopes, with quotes for each sector separated, or via the email address provided above under instructions to bidders. E.g. “**Rulindo– Buyoga – Rehabilitation services**”.
16. The bidder of the above service service **must be willing and capable of providing the services in the same district(s) where the rehabilitation services will take place.**
17. **The bidder is free to send quotations for any/all operations sites of his/her choice.**
18. Registered companies must submit the following documents for bidding:
- Copy of Company registration certificate.
 - Copy of Tax Clearance from RRA.
 - Proof of Electron Billing Machine invoice
 - A final fixed price for each of the services outlined in this solicitation.

Amendments:

If it becomes necessary to modify this RFP, an amendment will be issued and be binding to all bidders. Amendments(s) will be sent to all bidders with return receipt requested, and will be numbered consecutively commencing with Amendment-01, 02, etc. Bidders are required to reference such amendments in their subsequent response and/or communication.

Clarifications:

All questions with regard to this RFP shall be addressed to PMI_EvolveRwanda@abtglobal.com . Abt will communicate questions and responses to all bidders and may at its sole discretion extend the quotation deadline. Oral communication concerning this RFP will not be accepted except for administrative clarification regarding submission format or location of the office, etc.

**Quote Validity/Performance Period:**

Submitted offers/Bids shall be valid for at least a period of 30 days from RFP closing date.

Invoices and Payments:

Payments will be made after Abt Global receives a complete and correct invoice from supplier after completion of Services. The vendor should indicate the bank account on the printed invoice clearly.

Payments will be made net thirty (30) days after Abt Global receives a complete and correct EBM invoice from supplier based solely on Services actually performed by Supplier and/or Goods actually supplied by supplier pursuant to a Purchase or Delivery order. Abt Global issues all payments exclusively to the registered bank account of the contracted company. Payments will never be made to personal or individual bank account numbers. ***No advance payment should be expected by vendors from Abt Global.***

Evaluation Criteria:

Abt Global intends to award a PO (in whole or in part) to the most advantageous technically compliant offer(s), the following factors considered:

- Adherence to specifications and RFP instructions
- Payment terms
- Fixed Price
- Delivery Times

- Past performance (Note: New bidders are welcome. This criterion is used to eliminate supplier(s) with documented chronic performance issues).

A responsive proposal is one that comes from a responsible supplier and complies with all the terms and conditions stated in the RFP without material modification. A material modification is any modification that affects price, quantity, quality, delivery, or which limits in any way the responsibilities, duties or liabilities of the bidder or any rights of Abt or its clients.

Abt reserves the right to waive any minor informalities in the quotation/proposal received if it is in Abt's best interest to do so, or to reject the quotation of any firm if, in Abt's judgement, the firm is not fully qualified to provide the goods or services as specified in the technical specifications.

Abt Global LLC is an equal opportunity employer and strongly encourages women and women-led companies to apply for this tender.

Abt Global appreciates and values the involvement of local companies in this tender. Consequently, preference will be given to local businesses to the extent practical and within award criteria considered. Claims of local incorporation must be supported by a valid business license from the relevant district or region.



APPENDIX A: BID SHEET

#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
1. Nyamabuye Soak pit One Construction & Material (Muhanga District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					



Labor Charge (including transportation cost if any)	
Sub Total	
18%VAT	
GRAND TOTAL	

#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
2. Nyamabuye Soak pit Two Construction & Material (Muhanga District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1 metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		



6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-	
Total Price for Building Materials (excluding labor)				
Labor Charge (including transportation cost if any)				
Sub Total				
18% VAT				
GRAND TOTAL				

#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
3. Kabacuzi Site Construction & Material (Muhanga District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		



6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-	
Total Price for Building Materials (excluding labor)				
Labor Charge (including transportation cost if any)				
Sub Total				
18%VAT				
GRAND TOTAL				

#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
4. Kibangu Site Construction & Material (Muhanga District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		



5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					
Labor Charge (including transportation cost if any)					
Sub Total					
18% VAT					
GRAND TOTAL					

#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
5. Rugendabali Site Constriction & Material (Muhanga District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1 metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		



III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					
Labor Charge (including transportation cost if any)					
Sub Total					
18% VAT					
GRAND TOTAL					

#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
6. Kayumbu Site Construction & Material (Kamonyi District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1 metres)	Pit	1		
2	Sawdust	sac/100kg	2		



3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					
Labor Charge (including transportation cost if any)					
Sub Total					
18% VAT					
GRAND TOTAL					

#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
7. Masoro Site Construction & Material (Rulindo District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		



II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1 metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					
Labor Charge (including transportation cost if any)					
Sub Total					
18%VAT					
GRAND TOTAL					

#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
8. Murambi Site Construction & Material (Rulindo District)					
I	Preliminary works				



1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1 metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					
Labor Charge (including transportation cost if any)					
Sub Total					
18%VAT					
GRAND TOTAL					

#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
9. Buyoga Site Construction & Material (Rulindo District)					



I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence(4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					
Labor Charge (including transportation cost if any)					
Sub Total					
18%VAT					
GRAND TOTAL					



#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
10.Rutare Site Construction & Material (Gicumbi District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					
Labor Charge (including transportation cost if any)					
Sub Total					
18%VAT					
GRAND TOTAL					



#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
11.Bukure Site Constriction & Material (Gicumbi District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					
Labor Charge (including transportation cost if any)					
Sub Total					
18%VAT					
GRAND TOTAL					



#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
12. Bumbogo Site one/Soak pit number 1 Construction & Material (Gasabo District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1 metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					
Labor Charge (including transportation cost if any)					
Sub Total					
18%VAT					
GRAND TOTAL					



#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
13. Bumbogo Site one/Soak pit number 2 Construction & Material (Gasabo District) (Gasabo District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1 metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					
Labor Charge (including transportation cost if any)					
Sub Total					
18%VAT					
GRAND TOTAL					



#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
14. Bumbogo Site Two/Soak pit number 1 Construction & Material (Gasabo District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1 metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					
Labor Charge (including transportation cost if any)					
Sub Total					
18% VAT					
GRAND TOTAL					



#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
15. Bumbogo Site Two/Soak pit number 1 Construction & Material (Gasabo District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		
Total Price for Building Materials (excluding labor)					



Labor Charge (including transportation cost if any)		
Sub Total		
18%VAT		
GRAND TOTAL		

#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
14	Items	Unit	Quantity	Unit Price (Rwf)	Total Price (Rwf)
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		
6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-		



Total Price for Building Materials (excluding labor)	
Labor Charge (including transportation cost if any)	
Sub Total	
18%VAT	
GRAND TOTAL	

#	Specific Activity	Quoted Description	Quoted Description	Unit Price VAT exclusive	Total price with VAT exclusive
17. Muyumbu Site Two Construction & Material (Rwamagana District)					
I	Preliminary works				
1	Cleaning the surroundings of the soak pit (approximately 30 square meters)."	Square meter	30		
II	Setting up the Bio-bed				
1	Digging Soak Pit (2x1x1 metres)	Pit	1		
2	Sawdust	sac/100kg	2		
3	Charcoal	sac/100kg	3		
4	Gravels	Wheelbarrow	4		
5	Big stone	Wheelbarrow	6		
6	Small stone for pit	Wheelbarrow	4		
III	Fence (4*4)				
1	Wire mesh (iron steel wire, Stainless Steel wire 20 square meters)	Piece	1		
2	Wooden poles	Piece	17		
3	Wooden Door (90 x1.7m) with locking handle	pc	1		
4	Padlock (size medium)	Piece	1		
5	Nails, size 8 cm	Kg	2		
IV	2 BATHROOMS, TANK SUPPORT, DRY LINES SUPPORT CONSTRUCTION				
1	Wooden Poles for two bathrooms	Piece	12		
2	Wooden Poles for Hanging coveralls	Piece	2		
3	Nails, size 6-8 cm	kg	1.5		
4	Roofing nails, size 6-8 cm	Kg	1		
5	Small Stones for two bathrooms	Wheelbarrow	4		



6	Parking soil in 4 bags of 100kg (bed to support water tank)	-	-	
Total Price for Building Materials (excluding labor)				
Labor Charge (including transportation cost if any)				
Sub Total				
18% VAT				
GRAND TOTAL				



Attachment: A

Prime Contract Mandatory Flow Downs
(See separate attachment)

Attachment B:

Abt Standard Terms and Conditions
(See separate attachment)

Attachment: C

List of Exceptions (See separate attachment)

Attachment D:
Submission Checklist
(See separate attachments)